



Business & Financial Services Department
Telephone: 604-276-4097
Fax: 604-276-4162

May 17, 2010
File: 02-0775-50-3939/Vol 01

Dear Sir/ Madame,

Re: Addendum #3 3939Q – Hamilton Community Centre – Piling

The following change is hereby made a part of the Quote Documents as fully and wholly as if the same were fully set for the therein:

1. Who is responsible for installing the gravel access road and construction fencing referred in Addendum #1?

Site preparation and clearing shall be performed by contractors prior to commencing piling work.

2. What is the requirement for post-driving site reclamation?

Piling contractor shall leave the site level and clean of waste. Gravel work platforms introduced by the piling contractor are to be left in place.

3. The geotechnical report calls for the pre-augured holes to be 10 feet deep, while the HCMA drawings call for “at least 6 meters”. Please clarify.

Pre-augured holes shall be 10 feet deep.

4. What is the “Concrete supply and place” line item for in the Quotation Form (page 9).

Please provide a unit price for concrete supply and place for use on possible change orders that may occur.

5. Also please clarify the foundation excavation requirement in 1.6.6 of 02350.

Delete the following:

“Dispose of excavated material off the site. Cutting and removal of extra pile lengths (at cut-off elevation) after completion of foundation excavation by the Pile Contractor.”

And replace with the following:

“Pile Contractor to excavate as require to cut and remove any extra pile lengths to conform with required cut-off elevations.”

Yours truly,

A handwritten signature in black ink, appearing to read 'S. Dosanjh', written in a cursive style.

S Dosanjh
Buyer II - Contracting Specialist
City of Richmond