



# City of Richmond

June 15, 2010  
File: 10-6340-20-P.10402/Vol 01

**Business and Financial Services**  
Telephone: (604) 276-4097  
Fax: (604) 276-4162

TO THOSE WHO HAVE RECEIVED COPIES OF T.3922

Dear Sir/Madam:

**Re: Addendum No. 5  
Contract T.3922  
Watermain Replacement Program 2010 – Lulu East and West**

This addendum forms part of the Tender Documents and shall be read, interpreted and coordinated with all other parts. The costs of all work contained herein shall be included in the Tender Price.

Tenderers shall acknowledge receipt of this addendum by inserting its number and date where provided for in the Form of Tender.

The following revisions supersede the information contained in the original Tender Document to the extent referenced and shall become part thereof:

## **1. SUPPLEMENTARY GENERAL CONDITIONS**

### **1.1 Page D-6: SGC 12 – Construction Priorities - First Paragraph.**

After “The latter Work Area shall be scheduled to meet the Owner’s requirements in July or August 2010.” add the following “Gilley watermain must be completed before mid August 2010 in order to allow for City tie-ins before school starts in September 2010. The section between Westminster Hwy and Smith Dr may be constructed in July 2010. The section east of Smith Dr may not start until August 1, 2010. A minimum of one lane of traffic must be maintained at all times. Construction access to the Hamilton Community Centre on the south-east corner of the intersection of Smith Dr and Gilley Rd cannot be disrupted.”

## **2. CLARIFICATIONS**

**2.1** Note that Grind and Overlay cross sections in the Contract Drawings are not entirely consistent. All Grind and overlay on local roads with total asphalt thickness of 85mm shall be 40mm. All Grind and overlay on collector, arterial or bus routes with total asphalt thickness of 150mm shall be 50mm.

- 2.2 An additional approximately 35 metres of 300mm diameter PVC Class 150 (DR18) AWWA C900 is required for a sanitary forcemain crossing Gilley Road on the east side of Smith Dr as per the attached drawing (Hamilton Forcemain, Smith Crescent from Gates Avenue to Gilley Road).

### **3. FORM OF TENDER**

- 3.1 Page B-14 Schedule E, Gilley Watermains: Add Item E-W1 c) 300mm dia. Sanitary FM, Unit: lin. m., Est. Qtys.: 35 metres. Payment for this item is for supply and installation of the pipe. The unit price tendered shall include but not be limited to all materials, labour, and equipment, traffic control, excavation and disposal, shoring, dewatering, bedding, pipe installation, fittings, valves, air valve assemblies, restraining devices, corrosion protection, wrappings the joints, backfilling, grading, compaction, surface restoration, excluding final asphalt overlay, all as specified in the specifications or as shown on the drawings or as otherwise directed by and to the satisfaction of the Engineer. Pipe shall be capped at both ends and tested at 100psi.
- 3.2 Page B-14 Schedule E, Gilley Watermains: Add Item E-W6 Surface Restoration for Sanitary FM, Lump Sum. This item includes all the Contractor's costs for labour, material and equipment associated with the supply and installation of the final asphalt overlay in accordance with City Richmond Bylaw 7869 "Roadway Restoration Regulation" dated April 11, 2005.

Yours truly,



Sumita Dosanjh for Kerry Lynne Gillis  
*Buyer II - Contracting Specialist*

